

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18412/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Maintenance of Drilled BBMP Borewells in ward no 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				DEVARAJU K		
				In Figures		In Words
1	28	Lifting of Submersible pump set as per Specification and direction etc., complete and as per the directions of the Engineer-in-charge of the work	Each	808.0	22624.00	Rupees Eight Hundred Eight Only
2	28	Transportation of pumping machineries etc., complete and as per the directions of the Engineer-in-charge of the work	Each	855.0	23940.00	Rupees Eight Hundred Fifty Five Only
3	28	Labour charges (over hauling) etc., complete and as per the directions of the Engineer-in-charge of the work	Job	522.0	14616.00	Rupees Five Hundred Twenty Two Only
4	28	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. (Above 10 HP upto 20 HP add Rs.150/- for every HP) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4513.0	126364.00	Rupees Four Thousand Five Hundred Thirteen Only
5	28	Starter (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4797.0	134316.00	Rupees Four Thousand Seven Hundred Ninety
6	28	Rotor (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4465.0	125020.00	Rupees Four Thousand Four Hundred Sixty Five
7	28	Upper Flange etc., complete and as per the directions of the Engineer-in-charge of the work	No.	333.0	9324.00	Rupees Three Hundred Thirty Three Only
8	28	Lower Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	617.0	17276.00	Rupees Six Hundred Seventeen Only
9	28	Carbon Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	451.25	12635.00	Rupees Four Hundred Fifty One and Twenty
10	28	Thrust bearing block assembly complete with Segment bearing pad etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1093.0	30604.00	Rupees One Thousand Ninety Three Only
11	28	Oil Seal etc., complete and as per the directions of the Engineer-in-charge of the work	No.	119.0	3332.00	Rupees One Hundred Nineteen Only
12	28	Oil Seal Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	142.0	3976.00	Rupees One Hundred Forty Two Only
13	420	Guide vane etc., complete and as per the directions of the Engineer-in-charge of the work	No.	166.0	69720.00	Rupees One Hundred Sixty Six Only
14	420	Impeller Shell moulded with aluminium Bronze) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	403.0	169260.00	Rupees Four Hundred Three Only
15	28	Discharge outlet (D.O) Bearing D.O Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	422.0	11816.00	Rupees Four Hundred Twenty Two Only
16	28	Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	142.0	3976.00	Rupees One Hundred Forty Two Only
17	28	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	902.0	25256.00	Rupees Nine Hundred Two Only
18	28	Non - return valve (NRV) assembly complete with rubber 'O' Ring etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1282.0	35896.00	Rupees One Thousand Two Hundred Eighty Two Only
19	28	Cable Guard etc., complete and as per the directions of the Engineer-in-charge of the work	No.	142.0	3976.00	Rupees One Hundred Forty Two Only
20	28	Brass Filter etc., complete and as per the directions of the Engineer-in-charge of the work	No.	237.0	6636.00	Rupees Two Hundred Thirty Seven Only
21	15	Re-erection charges of pumping machineries including overhauling and pointing etc., complete and as per the directions of the Engineer-in-charge of the work	Each	903.0	13545.00	Rupees Nine Hundred Three Only

12/2/16


Executive Engineer
 Byatarayanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				DEVARAJU K		
				In Figures		In Words
22	50	Supplying of ISI marked galvanized mild steel tube (continuously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threafes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	360.0	18000.00	Rupees Three Hundred Sixty Only
23	15	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	123.5	1852.50	Rupees One Hundred Twenty Three and Fifty
24	200	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	185.0	37000.00	Rupees One Hundred Eighty Five Only
25	30	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.P No. 68/ I No. 4(d) 4 core 16 Sqmm etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	133.0	3990.00	Rupees One Hundred Thirty Three Only
26	30	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, P No. 69 / I No. 1a In existing trencg/duct 6Sqmm to 16 Sqmm) etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	10.3	309.00	Rupees Ten and Thirty Paise Only
27	20	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR KSRB 1-2 P-7) etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	80.0	1600.00	Rupees Eighty Only
28	16	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	327.0	5232.00	Rupees Three Hundred Twenty Seven Only
29	4	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	266.0	1064.00	Rupees Two Hundred Sixty Six Only
30	36	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete and as per the directions of the Engineer-in-charge of the work	No.	175.0	6300.00	Rupees One Hundred Seventy Five Only
31	2	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1500.0	3000.00	Rupees One Thousand Five Hundred Only
32	2	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spotetc., complete and as per the directions of the Engineer-in-charge of the work	No	220.0	440.00	Rupees Two Hundred Twenty Only

12/2/16

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

26/2/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				DEVARAJU K		
				In Figures		In Words
33	23400	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.33 etc., complete and as per the directions of the Engineer-in-charge of the work	Sq Cm	0.32	7488.00	and Thirty Two Paise Only
					950383.50	

(E 200)

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
26/4/16